

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-01467-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 10-17S-11W
990 feet from N Section Line, 2310 feet from E Section Line
Lease Name: KRAFT Well #: K-1 (A)
County: BARTON Total Vertical Depth: 3298 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3264		unsure of depth
PROD	7	3288		125 SX
SURF	10.75	220		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/15/2015 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR Phone: (620) 275-9231

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 18 sx gel and 500 # hulls.
Well showed 7" casing but when dug out 5 1/2" casing was welded into 7" casing. Casing size is unknown. Plugged well as having 7" casing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/16/2015 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 665' and 200'. Ran tubing to 3200' and pumped 18 sx gel followed by 100 sx cement w/200 # hulls. Pulled tubing to 1450'. Circulated cement to surface w/200 sx cement on casing and surface pipe. Pulled tubing and topped off w/75 sx cement.

GPS: 38.41909 -098.55797

Perfs:

Top	Bot	Thru	Comments
3288	3298	OH	

Remarks: ALLIED CEMENT CO

Plugged through: CSG

District: 04

Signed
KCC WICHITA

FEB 08 2015

RECEIVED

Bruce Rodie
(TECHNICIAN)

2/11/15 CKM

CM

JAN 27 2015