

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-21362-00-01
Spot: NESWSENE Sec/Twnshp/Rge: 26-18S-21W
2980 feet from S Section Line, 700 feet from E Section Line
Lease Name: RYERSEE Well #: 1-E
County: NESS Total Vertical Depth: 4168 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1300		
PROD	5.5	4162	0	WITH 200 SX CMT
SURF	8.625	290		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/20/2015 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: SANDED TO 4000' WITH 5 SX CMT. CIBP @ 1300'. SWABBED CASING DOWN TO 1300'. PUT SWEDGE ON AND FILL WITH CMT. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 01/20/2015 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED TO 4000' WITH 5 SX CMT. RUN BOND LOG & FOUND CMT 1400' TO SURFACE. SET CIBP @ 1300'. SWABBED CASING TO 1300'. PUT SWEDGE ON CASING AND PUMPED 120 SX CMT DOWN CASING. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. PRESSURED TO 400#. SHUT IN.

Perfs:

Top	Bot	Thru	Comments
4095	4096		
4080	4088		

KCC WICHITA
FEB 06 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

2/11/15 ckm

RECEIVED
JAN 29 2015
KCC DODGE CITY