

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-22168-00-00  
Spot: NWNENE Sec/Twnshp/Rge: 7-27S-12W  
333 feet from N Section Line, 982 feet from E Section Line  
Lease Name: POLLOCK Well #: 4  
County: PRATT Total Vertical Depth: 4335 feet

Operator License No.: 31056  
Op Name: BULLSEYE OILFIELD SERVICE  
Address: 10308 NE 30TH AVE PO BOX 8778  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4326	2140	WITH 190 SX CMT
SURF	8.625	371		WITH 275 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/06/2015 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 4130' WITH 2 SX CMT OR SAND TO 4130' & 5 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/07/2015 12:30 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SANDED TO 4043' WITH 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. TAGGED TOC @ 4050'. 1ST PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 420' WITH 50 SX CMT. DID NOT CIRCULATE. PULLED TO 340' & PUMPED 50 SX CMT. TAGGED TOC @ 392'. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4184	4188		

KCC WICHITA  
FEB 06 2015  
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

2/11/15 CCM

District: 01

Signed

*Robert Dickerson*

(TECHNICIAN)

RECEIVED  
JAN 26 2015  
KCC DODGE CITY

Form CP-2/3