

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-06955-00-02
Spot: E2NWNW Sec/Twnshp/Rge: 23-14S-14W
4620 feet from S Section Line, 4290 feet from E Section Line
Lease Name: GURNEY A Well #: 4
County: RUSSELL Total Vertical Depth: 3014 feet

Operator License No.: 34912
Op Name: C12 KANSAS OIL, LLC
Address: 1900 WAZEE ST. SUITE 200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2974		50 SX
SURF	10.75	355		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2015 10:30 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: RICHARD PANCAKE Company: C-12 KANSAS OIL, LLC Phone: (785) 292-3515

Proposed Plugging Method: Ordered 600 sx 60/40 pozmix 4% gel cement, 600 # hulls and 8 sx gel.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/22/2015 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforations: 300' and 910'. Ran tubing to 2974' and pumped 160 sx cement w/150 # hulls. Pulled tubing to 2000' and pumped 8 sx gel. Pulled tubing to 1472' and pumped 220 sx cement w/150 # hulls. Cement circulated. Pulled tubing to 320' and pumped 10 sx cement and re-filled casing. POOH and topped off w/10 sx cement. Checked on fill up on 01/23/2015.

GPS: 38.82559 -098.85155

Perfs:

Top	Bot	Thru	Comments
2974	3014		
2377	2382		
2351	2356		

Remarks: QUALITY CEMENTING TICKET # 6320

Plugged through: TBG

2/11/15 ckm

District: 04

Signed

Ray A Dinkel

KCC WICHITA

(TECHNICIAN)

cm

FEB 06 2015

RECEIVED

JAN 26 2015