

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-22472-00-00  
Spot: NENENE Sec/Twnshp/Rge: 3-34S-14W  
413 feet from N Section Line, 344 feet from E Section Line  
Lease Name: WHEAT A Well #: 1-3  
County: BARBER Total Vertical Depth: 5296 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4660		WITH 2 SX CMT
CIBP		4950		WITH 2 SX CMT
PROD	5.5	5296	2681	WITH 310 SX CMT
SURF	8.625	1041		WITH 750 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/28/2015 1:15 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 5160' WITH 2 SX CMT. SET CIBP @ 4660' WITH 2 SX CMT. PLUG AT 1080' WITH 15 SX GEL & 50 SX CMT. PLUG AT 540' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/28/2015 1:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4950' WITH 2 SX CMT. SET CIBP @ 4660' WITH 2 SX CMT. 1ST PLUG AT 1079' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 539' WITH 40 SX CMT. 3RD PLUG AT 63' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5208	5212		
4716	4834		

KCC WICHITA  
FEB 06 2015  
RECEIVED


Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

2/11/15 CKM

District: 01

Signed

  
(TECHNICIAN)

RECEIVED  
JAN 30 2015  
KCC DODGE CITY