

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-081-21020-00-00  
Spot: NENE Sec/Twnshp/Rge: 26-28S-34W  
623 feet from N Section Line, 770 feet from E Section Line  
Lease Name: MCCOY Well #: 3-26  
County: HASKELL Total Vertical Depth: 4950 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4118		WITH 2 SX CMT
CIBP		4174		
CIBP		4320		
CIBP		4500		
PROD	4.5	4650	1917	WITH 490 SX CMT
SURF	8.625	1854		WITH 850 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/28/2015 2:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 4118' WITH 2 SX CMT. PLUG AT 1890' WITH 15 SX GEL & 50 SX CMT. PLUG AT 750' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/29/2015 4:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4118' WITH 2 SX CMT. 1ST PLUG AT 1898' WITH 50 SX CMT. 2ND PLUG AT 747' WITH 40 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4168	4172		

KCC WICHITA  
FEB 06 2015  
RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
JAN 30 2015  
KCC DODGE CITY

Signed \_\_\_\_\_

(TECHNICIAN)

2/11/15 ckm