

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-30025-00-00
Spot: NESW Sec/Twnshp/Rge: 32-33S-31W
1909 feet from S Section Line, 3279 feet from E Section Line
Lease Name: DAVIES Well #: 1
County: SEWARD Total Vertical Depth: 6079 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5726		WITH 2 SX CMT
PROD	4.5	6075	1538	WITH 300 SX CMT
SURF	8.625	1454		WITH 675 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/29/2015 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: SET CIBP @ 5726' WITH 2 SX CMT. PLUG AT 1490' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 01/29/2015 1:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 5726' WITH 2 SX CMT. 1ST PLUG AT 1511' WITH 15 SX GEL & 75 SX CMT.
NO RETURNS. TAG TOC @ 1470'. 2ND PLUG AT 1440' WITH 40 SX CMT. 3RD PLUG
AT 650' WITH 40 SX CMT. 4TH PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5776	5784		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed _____

Kenny Sullivan

(TECHNICIAN)

2/11/15 ckm

RECEIVED
JAN 30 2015
KCC DODGE CITY

KCC WICHITA

FEB 06 2015

RECEIVED

Form CP-2/3

Kms