

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-25516-00-00
Spot: E2NESE Sec/Twnshp/Rge: 3-12S-16W
2040 feet from S Section Line, 400 feet from E Section Line
Lease Name: DREILING F Well #: 34
County: ELLIS Total Vertical Depth: 3420 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3405		175 SX
SURF	8.625	223		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2015 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: IVAN R. EDSALL Company: DREILING OIL INC. Phone: (785) 625-8327

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/200 # hulls.
DV Tool at 952' w/460 sx cement.
Cong- 3288' - 3296' and ARB- 3325' - 3336' OA

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/22/2015 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service ran in hole with tubing to 3323' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 2850' and pumped 100 sx cement w/200 # hulls mixed in. Pulled tubing to 1800' and pumped 100 sx w/100 # hulls mixed in. Pulled tubing to 900' and pumped 100 sx cement to circulate cement to surface. Pulled tubing. Topped off 5 1/2" casing w/15 sx cement. Hole standing full. Rigged to 8 5/8" surface pipe and pumped 5 sx cement to pressure w/200 psi. Shut in pressure 200 psi.

GPS: 39.03635 -099.07675
2062' FSL 393' FEL
SW NE NE SE

Perfs:

Top	Bot	Thru	Comments
3334	3336		
3326	3329		
3288	3296		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1079

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

KCC WICHITA

FEB 06 2015

RECEIVED

2/11/15 ckm

cm

JAN 26 2015