

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-23962-00-00
Spot: E2W2SW Sec/Twnshp/Rge: 3-17S-12W
1320 feet from S Section Line, 4290 feet from E Section Line
Lease Name: STUMPS B Well #: 3
County: BARTON Total Vertical Depth: 3335 feet

Operator License No.: 3309
Op Name: EAGLE PETROLEUM, INC.
Address: PO BOX 335
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3331		150 SX
SURF	8.625	330		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/15/2015 12:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RON HICKEL Company: EAGLE PETROLEUM Phone: (620) 793-2037

Proposed Plugging Method: Ordered 12 sx gel, 350 sx 60/40 pozmix 4% gel cement and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/15/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 760' and 300'. Ran tubing to 3286' and pumped 12 sx gel followed by 65 sx cement w/100 # hulls. Pulled tubing to 1456' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 760'. Circulated cement to surface w/120 sx cement and 200 # hulls. Pulled tubing. Hole standing full. Tied to surface pipe and pumped 10 sx cement and pressured up.

GPS: 38.59809 -098.64218

Perfs:

Top	Bot	Thru	Comments
3210	3220		
3136	3140		
3100	3106		
3074	3080		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie 2/11/15 CEM
KCC WICHITA (TECHNICIAN) CM

FEB 06 2015

RECEIVED

JAN 27 2015