

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25321-00-00
Spot: NWENW Sec/Twnshp/Rge: 22-17S-12W
425 feet from N Section Line, 1665 feet from W Section Line
Lease Name: ANNA Well #: "B" 1
County: BARTON Total Vertical Depth: 3425 feet

Operator License No.: 33527
Op Name: J D DREILING OIL, INC.
Address: 215 6TH ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3424		135 SX
SURF	8.625	400		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/21/2015 7:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAN A DREILING Company: JD DREILING OIL Phone: (620) 587-3658

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2015 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

01/21/2015- Pumped 60 sx cement at 3300'.
01/22/2015- Cut casing at 2220'. Pulled casing to 1500' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 40 sx cement w/100 # hulls. Pulled casing to 650' and pumped 40 sx cement w/100 # hulls. Pulled casing to 400'. Circulated cement to surface w/100 sx cement. Pulled casing and hole stayed full.

GPS: 38.56431 -098.63991

Perfs:

Top	Bot	Thru	Comments
3340	3355		
3164	3168		
3151	3156		
3087	3090		
3016	3022		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

2/11/15 CKM

District: 04

Signed Bruce Rodie
KCC WICHITA (TECHNICIAN) CM

JAN 27 2015

FEB 06 2015
RECEIVED