

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25000-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 10-16S-14W
2310 feet from N Section Line, 2430 feet from E Section Line
Lease Name: KARST POPP UNIT Well #: 1
County: BARTON Total Vertical Depth: 3450 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3446		140 SX
SURF	8.625	435		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/26/2015 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS Phone: (214) 219-8883

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 1798'. Pulled casing to 1500' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 60 sx cement w/100 # hulls. Pulled casing to 400'. Circulated cement to surface w/100 sx cement and 100 # hulls. Pulled casing. Hole stayed full.
GPS: 38.67491 -098.85765

Perfs:

Top	Bot	Thru	Comments
3339	3343		
3315	3319		
3308	3310		
3296	3300		
3278	3282		
3216	3300		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

2/11/15 CKM

District: 04

Signed Bruce Rodie
(TECHNICIAN) *CM*

KCC WICHITA

FEB 06 2015

RECEIVED

JAN 27 2015