

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-19087-00-00
Spot: SENE SW Sec/Twnshp/Rge: 16-14S-14W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: COADY Well #: 5
County: RUSSELL Total Vertical Depth: 3310 feet

Operator License No.: 8996
Op Name: MID-CONTINENT RESOURCES, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3225		100 sx
SURF	8.625	877		340 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/26/2015 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: MID-CONTINENT Phone: (620) 275-2963

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2015 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 840' and 1575'. Ran tubing to 3040' and stacked out. Pulled tubing back to 3012' and pumped 1000 psi to get the tubing cleaned out. Pumped 75 sx cement w/150 # hulls. Both backside and braden head circulated fluids out. Pulled tubing to 2262' and pumped 100 sx cement. Pulled tubing to 1260' and pumped 100 sx cement. Cement circulated. POOH. Hooked to casing and pumped 100 sx cement. Cement circulated out of the braden head. Shut in.

GPS: 38.83157 -098.88388

Perfs:

Top	Bot	Thru	Comments
3044	3166		

Remarks: SWIFT SERVICES TICKET # 27082

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

KCC WICHITA

CM

2/11/15 ckm

JAN 27 2015

FEB 06 2015

Form CP-2/3

RECEIVED