

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-08232-00-00
Spot: SESENW Sec/Twnshp/Rge: 15-14S-15W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ROUBACK Well #: 1-B
County: RUSSELL Total Vertical Depth: 3225 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3218		250 SX
SURF	15	300		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/26/2015 12:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL Phone: (620) 938-2943

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 18 sx gel and 1000# hulls. 3% C.C. on the side.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2015 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 840' and 1450'. Ran tubing to 3100' and pumped 18 sx gel followed by 50 sx cement w/50 # hulls. Well circulating fluids. Pulled tubing to 1500' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 880' and pumped 175 sx cement. Cement circulated. POOH. Topped off w/25 sx cement. Hole stayed full.
01/27/2015- Checked fill up.
GPS: 38.838541 -098.97659

Perfs:

Top	Bot	Thru	Comments
3216	3225		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

2/11/15 CLKM

District: 04

Signed Ray A. Dinkel
KCC WICHITA (TECHNICIAN) C/M

JAN 27 2015

FEB 06 2015

Form CP-2/3

RECEIVED