

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23675-00-01
Spot: NWNWNW Sec/Twnshp/Rge: 31-16S-21W
4917 feet from S Section Line, 4682 feet from E Section Line
Lease Name: THOMPSON B Well #: 4
County: NESS Total Vertical Depth: 4420 feet

Operator License No.: 31086 String Size Depth (ft) Pulled (ft) Comments
Op Name: RICHLAN DRILLING, A GENERAL PAR PROD 5.5 4419 0 WITH 100 SX CMT
Address: 598 2ND AVE SURF 8.625 265 WITH 150 SX CMT
BEAVER, KS 67525

Well Type: EOR UIC Docket No: E27671.2 Date/Time to Plug: 01/23/2015 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICK SCHREIBER Company: RICHLAN DRILLING Phone: (620) 587-3605

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 01/23/2015 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4250' & PUMPED 200# HULLS & 35 SX CMT. PULLED TBG TO 1690' & PUMPED 181 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 12 SX CMT. TIED ONTO BACKSIDE & PUMPED 2 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4277	4296		

KCC WICHITA
FEB 06 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

2/11/15 CKM

District: 01

Signed Michael Maier
(TECHNICIAN)

cc:UIC ✓

RECEIVED
JAN 29 2015
KCC DODGE CITY

km5