

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-01017-00-01
Spot: SESENE Sec/Twnshp/Rge: 8-14S-13W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: DUMLER OWWO Well #: 2
County: RUSSELL Total Vertical Depth: 3380 feet

Operator License No.: 33905
Op Name: ROYAL DRILLING INC
Address: 719 WITT AVE PO BOX 342
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2470		100 SX
SURF	8.625	442		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/20/2015 10:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: JOHN DRISCOLL Company: ROYAL DRILLING INC Phone: (785) 483-9580

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/20/2015 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 1820'. Pulled casing to 1500' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/200 # hulls. Pulled casing to 400'. Circulated cement to surface w/125 sx cement and 200 # hulls. Pulled casing and topped off w/50 sx cement.

GPS: 38.85016 -098.78193

Perfs:

Remarks: ALLIED CEMENTING CO

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

2/11/14 OKM

CM

KCC WICHITA

FEB 06 2015

RECEIVED

Form CP-2/3

JAN 27 2015