

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-21544-00-00
Spot: NWSESE Sec/Twnshp/Rge: 8-14S-13W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: CARTER Well #: 3
County: RUSSELL Total Vertical Depth: 2580 feet

Operator License No.: 33905
Op Name: ROYAL DRILLING INC
Address: 719 WITT AVE PO BOX 342
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2575		100 SX
SURF	8.625	211		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/21/2015 10:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: JOHN DRISCOLL Company: ROYAL DRILLING INC Phone: (785) 483-9580

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Sanded off perforations and topped with cement to pull casing. Could not get any stretch on casing. Will plug through tubing.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/22/2015 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1500', 825' and 200'. Ran tubing to 1500' and pumped 70 sx cement. Pulled tubing to 850'. Circulated cement on casing and surface pipe w/50 sx cement. Pulled tubing. Hole stayed full.
01/22/2015- Topped off w/65 sx cement.

GPS: 38.84566 -098.78421

Remarks: ALLIED CEMENTING CO

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

2/11/15 CKM

CM

KCC WICHITA

FEB 06 2015

RECEIVED

Form CP-2/3

JAN 27 2015