

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-21419-00-00
Spot: E2SWSWSW Sec/Twnshp/Rge: 19-15S-25W
660 feet from S Section Line, 660 feet from W Section Line
Lease Name: DEINES M Well #: 1
County: TREGO Total Vertical Depth: 4525 feet

Operator License No.: 31514
Op Name: THOROUGHbred ASSOCIATES L.L.C.
Address: 8100 E 22ND ST STE 600
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7.875	4524		175 SX
SURF	12.25	347		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2015 10:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: BOBBY PATTON Company: EXPRESS WELL SERVICE & SUPPL Phone: (316) 685-1512

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gle cement w/500 # hulls.
Perforations at 4408' - 4435'.
Shot perforations at 325', 1000', 1940' and 2450'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/22/2015 2:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4310' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 3300' and pumped 75 sx cement. Pulled tubing to 2250' and pumped 200 sx cement. Good circulation of cement out of casing and backside. Pulled tubing out and topped off w/40 sx cement full.

GPS: 38.72733 -100.15200

Perfs:


Top	Bot	Thru	Comments
4408	4435		

Remarks: ALLIED CEMENT TICKET # 055625

Plugged through: TBG

District: 04

Signed



KCC WICHITA

(TECHNICIAN)

CM

JAN 26 2015

FEB 06 2015

RECEIVED

Form CP-2/3