

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-21985-00-00
Spot: NESW Sec/Twnshp/Rge: 13-19S-26W
1980 feet from S Section Line, 1980 feet from W Section Line
Lease Name: AYERS Well #: 1
County: NESS Total Vertical Depth: 4610 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: PO BOX 544 N HWY 283
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4600	0	WITH 100 SX CMT
SURF	8.625	654		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2014 9:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE J.FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 12/29/2014 10:50 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PRODUCTION CASING BROKE 6' BELOW SURFACE. PUMPED 25 SX CMT WITH 200# HULLS ON BOTTOM. PULLED TBG TO 1920' & PUMPED 130 SX CMT, CIRCULATING CMT TO SURFACE. TIED ONTO BACKSIDE & TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4601	4604	OH	

KCC WICHITA
FEB 06 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

2/11/15 ckm

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
JAN 26 2015
KCC DODGE CITY

km5