

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-22227-00-00  
Spot: E2W2NW Sec/Twnshp/Rge: 4-34S-13W  
3955 feet from S Section Line, 4605 feet from E Section Line  
Lease Name: FALEN Well #: 1  
County: BARBER Total Vertical Depth: 5050 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5047	0	WITH 225 SX CMT
SURF	8.625	389		WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/24/2015 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE  
Date/Time Plugging Completed: 01/24/2015 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMP 200# HULLS & 25 SX CMT AT 4769'. RAN CBL. TOC @ 290'. RAN TBG TO 800' & SPOTTED 25 SX CMT. PERFORATE AT 220' & CIRCULATE CMT TO SURFACE WITH 85 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4945	4967		
4861	4881		
4849	4853		

KCC WICHITA  
FEB 06 2015  
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

2/11/15ckm

District: 01

Signed

Stephen Pfeifer  
(TECHNICIAN)

RECEIVED  
JAN 30 2015  
KCC DODGE CITY