

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-22233-00-01
Spot: SESWNW Sec/Twnshp/Rge: 12-24S-11W
2986 feet from S Section Line, 3961 feet from E Section Line
Lease Name: ZENITH W F Well #: ZU 29W
County: STAFFORD Total Vertical Depth: 3855 feet

Operator License No.: 32699
Op Name: ZU, LLC
Address: 108 W 34TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2958		WITH 2 SX CMT
PROD	5.5	3855	1450	WITH 175 SX CMT
SURF	8.625	263		WITH 175 SX CMT

Well Type: EOR UIC Docket No: E12893.9 Date/Time to Plug: 01/15/2015 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: GREG WHITEHAIR Company: ZU, LLC Phone: (785) 432-0789

Proposed Plugging Method: CIBP @ 2958' WITH 2 SX CMT. PERFORATE AT 600' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: PARTIAL
Date/Time Plugging Completed: 01/15/2015 7:30 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

PACKER STUCK AT 3680'. LEFT IN HOLE: PACKER & 22 JOINTS 2 7/8" TBG
SET CIBP @ 2958' WITH 2 SX CMT ON TOP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. TOPPED OFF WITH 20 SX CMT

Perfs:

Top	Bot	Thru	Comments
3720	3746		

KCC WICHITA
FEB 06 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

Plugged through: CSG

2/11/15 ckm

District: 01

Signed Robert Dickerson

(TECHNICIAN)

CC:UIC ✓

SP

RECEIVED
JAN 28 2015
KCC DODGE CITY