

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-20643-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 22-34S-21W  
1650 feet from N Section Line, 2310 feet from E Section Line  
Lease/Unit Name: BARBY-HARPER Well Number: 8-22  
County: CLARK Total Vertical Depth: 4400 feet

Operator License No.: 5055  
Op Name: C. H. TODD, INC.  
Address: 1000 N. TYLER  
WICHITA, KS 67212

Conductor Pipe Size: 20 feet: 77 WITH 60 SX CMT  
Conductor Pipe Size: 13.375 feet: 319 WITH 600 SX CMT  
Production Casing Size: 5.5 feet: 4399 WITH 150 SX CMT  
Surface Casing Size: 8.625 feet: 813 WITH 600 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/08/2003 11:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC. *#143*  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4250' WITH 5 SX. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/08/2003 12:05 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 4356'. PERFS AT 4290-97'. SAND TO 4250' WITH 5 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 200#.

RECEIVED RECEIVED  
SEP 15 2003 SEP 15 2003  
KCC WICHITA DC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3100' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

(TECHNICIAN)

INVOICED

DATE 9-15-03

INV. NO. 2004060501

Form CR-23