

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20334-00-00
Spot: SWSW Sec/Twnshp/Rge: 22-34S-21W
660 feet from S Section Line, 660 feet from W Section Line
Lease/Unit Name: GWENDA LEA Well Number: 1
County: CLARK Total Vertical Depth: 5565 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N. TYLER
WICHITA, KS 67212

Production Casing Size: 5.5 feet: 5565 WITH 300 SX CMT
Surface Casing Size: 8.625 feet: 797 WITH 400 SX CMT

#180⁸⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/04/2003 1:20 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4200' & 5 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/04/2003 1:55 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:
PBTD 4350'. PERFS AT 4284-94'. SAND TO 4200' WITH 5 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 400#.


RECEIVED
SEP 10 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3000' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
SEP - 5 2003
KCC Dodge City

Signed 

(TECHNICIAN)

INVOICED
DATE 9-10-03
C.C. NO. 2004060489


Font CP 1/3