



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

6-january 1982

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

15-025-20,086-00-01

Dear Sir:

Mr. Jerry Young of Rine Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Rine Drilling Co. (drilled 9-4-75 by Pinon Production)

Complete Address: Suite 600, 300 W. Douglas Wichita Kans 67202

Lease Name: Barby - Harper Well No. 1-22

Location: NW-8W Sec. 22 Twp. 34 Rge. 21 (E) (W)

County: Clark Total Depth: 5600'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Young was instructed to plug the well as follows:

There is 720' of 8 5/8" surface casing cement circulated. They ran 5600' of 5 1/2" production pipe cemented. They had plugged back to 5450' with perforations at 4265' to 4275'. They squeezed the perforations and cemented with 150 sby of cement plugging hole back to 3970'. 1st plug pumped in 5 sby of hulls + 5 sby of gells, released rubber plug + pumped 50 sby of cement on top of it 2nd plug 40' to 0' with 10 sby of cement. Plugging accomplished by Halliburton Co. Cement used by Halliburton Co. They recovered 1970' of 5 1/2" production pipe.

Very truly yours,

Paul Luttich

Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

JAN 12 1982

CONSERVATION DIVISION  
Wichita, Kansas