



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 9 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Dunkin of Ashland Oil has this

date requested permission to plug the following described well:

Mr. Dunkin guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma City, Okla.

Lease Name: J.C. Harper Well No. 4

Location: SE SW Sec. 3 Twp. 34 Rge. 21 (E) (W)

County: Clark Total Depth 5500 bit Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dunkin was instructed to plug the well as follows:

13 3/8" to 498' circulated w/ cement. 8 5/8" to 2360' cemented.

5 1/2" to 5492' cemented. Top perforations 5382'

Plug bottom w/ 30 sacks cement Top of cement 5000'

Mud 5000' to 490' Spot 50 sacks cement 490' to 390'

Mud 390' to 40' Plug, H^ulls & 20 sacks cement 40' to 0'.

Very truly yours,

Edmund J. Evers
 Conservation Division Agent