



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 12 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dunkin of Ashland Oil & Refining has this date requested permission to plug the following described well:

Mr. Dunkin guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma City, Oklahoma

Lease Name: J.C. Harper Well No. 6

Location: NW NE Sec. 3 Twp. 34 Rge. 21 (W)

County Clark Total Depth 5596' Oil Well

Gas Well    Input Well    SWD Well X D & A X Lost Hole   

Mr. Dunkin was instructed to plug the well as follows:

13 3/8" to 501' circulated w/ cement. 8 5/8" to 2359' cemented.


5 1/2" to 5567' cemented. Top perforations 5406'

Plug bottom w/ 25 sacks cement Top of cement 5100'

Mud 5100 to 500' Spotted 50 sacks cement 500' to 400'

Mud 400' to 40' Plug, Hulls & 20 sacks cement 40' to 0'

Very truly yours,

  
Conservation Division Agent