



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 20 1968  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dunkin of Ashland Oil & Refin. has this

date requested permission to plug the following described well:

Mr. Dunkin guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma City, Oklahoma

Lease Name: J.C. Harper Well No. 8

Location: NE NE Sec. 3 Twp. 34 Rge. 21 (W)

County Clark Total Depth 5590' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Dunkin was instructed to plug the well as follows:

13 3/8" to 400' circulated w/ cement. 8 5/8" to 2312' cemented

5 1/2" to 5590' cemented. Top perforations 5426'

Plug bottom w/ 30 sacks cement Top of cement 5000'

Mud 5000' to 400' Spotted 50 sacks cement 400' to 300'

Mud 300' to 45' Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Conservation Division Agent