



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 19 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Duncan of Ashland Oil has this

date requested permission to plug the following described well:

Mr. Duncan guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Co.

Complete Address: Box 18695, Oklahoma City, Oklahoma

Lease Name: J.C. Harper Well No. 15

Location: SW NW Sec. 3 Twp. 34 Rge. 21 (X) (W)

County Clark Total Depth 5510' Oil Well X

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Duncan was instructed to plug the well as follows:

13 3/8" to 500' circulated w/ cement. 8 5/8" to 2385' cemented.

5 1/2" to 5510' cemented. Top perforations 5402'

Plug, bottom w/ 30 sacks cement. Top of cement 4800'

Mud 4800' to 500' Spot 50 sacks cement 500' to 400'

Mud 400' to 40' Plug, Hulls & 20 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent