



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 18 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dunkin of Ashland Oil has this

date requested permission to plug the following described well:

Mr. Dunkin guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma City, Oklahoma

Lease Name: M. C. Harper Well No. 1

Location: NW SE Sec. 4 Twp. 34 Rge. 21 (E) (W)

County: Clark Total Depth 5533' Oil Well

Gas Well Input Well SWD Well X D & A X Lost Hole

Mr. Dunkin was instructed to plug the well as follows:

13 3/8" to 489' circulated w/ cement. 8 5/8" to 2969' cemented.

5 1/2" to 5530' cemented. Top perforations 5420'

Plug bottom w/ 30 sacks cement Top of cement 4998'

Mud 4998' to 490' Spot 50 sacks cement 490' to 390'

Mud 390' to 40' Plug, Halls & 20 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Evers
Conservation Division Agent