



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 24 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dunkin of Ashland Oil & Refin. has this  
date requested permission to plug the following described well:

Mr. Dunkin guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Company

Complete Address: Box 18695, Okla. City, Okla.

Lease Name: M.C. Harper Well No. 4

Location: NE NE Sec. 4 Twp. 34 Rge. 21 (E) (W)

County Clark Total Depth Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dunkin was instructed to plug the well as follows:

13 3/8" to 489' circulated w/ cement. 8 5/8" to 2363' cemented

5 1/2" to 5500' cemented Top perforations 5393'

Plug bottom w/ 25 sacks cement Top of cement 4300'

Mud 4300' to 500' Spotted 50 sacks cement 500' to 400'

Mud 400' to 45' Plug, Hulls & 20 sacks cement 45' to 0'

Very truly yours,

Edgar J. Ford  
Conservation Division Agent