

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-025-20086-00-01

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Rine Drilling Co (drilled 9-4-75 by Pinion Pro.)

Complete Address Suite 600 300 W. Douglas Wichita Kansas 67202

Lease Name Barby Harper Well No. 1-23

Location NW-SW Sec. 22 Twp. 34 Rge. 21W (East)(West)

County Clay Total Depth 5600'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Rine Drilling Co.

Address Suite 600, 300 W. Douglas Wichita, Kans. 67202 License No. _____

Operation Completed: Hour: 5:30 PM Day: 8 Month: January Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 720' of 8 1/8" surface casing cement circulated. There was 5600' of 5 1/2" production pipe cemented. They plugged back to 5450'. Perforations were from 4265' to 4275'. They squeezed the perforations & cemented with 150 Sbs of cement plugging holdback to 3970'. 1st plug pumped in 5 Sbs of hulls & 5 Sbs of gel then released plug and pumped 50 Sbs of cement. 2nd plug 40' to 0' with 10 Sbs of cement. The plugging was accomplished by Halliburton Co. Cement was 229 lbs 2% cc. They recommend 1970' of 5 1/2" production pipe.

RECEIVED
JAN 12 1982
1-12-82

I hereby certify that the above plugging instructions were given as herein stated.

DATE 2-3-82
INV. NO. 9166-W

Signed: Paul Luther
Conservation Division Agent