

15-025-10135-00-00

Form CP-3
Rev. 6-26-62

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma City, Oklahoma 73118

Lease Name J.C. Harper Well No. 3

Location C SE NW Sec. 3 Twp. 34 Rge. 21 (W)

County Clark Total Depth 5477'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Gayle E. Toland

Address: Box 94336, Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 2:00PM Day 3 Month 7 Year 1968

The Above well was plugged as follows:

13 3/8" to 492' circulated w/ cement. 8 5/8" to 2384' cemented.

5 1/2" to 5477' cemented. Top perforations 5380'

Plug bottom w/ 30 sacks cement Top of cement 4800'

Mud 4800' to 490' Spotted 50 sacks cement 490' to 390'

Mud 390' to 45' Plug, Hulls & 20 sacks cement 45' to 0'

Company Pump Pulled 1244' of 8 5/8" casing.

Pulled 3735' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edgar Eves*
Well Plugging Supervisor

INVOICED

DATE 7/9/68

INV. NO. 8061-W