

15-025-10138-00-00

Form CP-3
Rev. 6-26-62

KANSAS

Y

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma City, Oklahoma

Lease Name J.C. Harper Well No. 6

Location NW NE Sec. 3 Twp. 34 Rge. 21 ~~22~~ (W)

County Clark Total Depth 5596'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A X

Other well as hereafter indicated: None

Plugging Contractor: Gayle E. Toland

Address: Box 94336, Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 3:00PM Day 10 Month 6 Year 1968

The Above well was plugged as follows:

13 3/8" to 501' circulated w/ cement. 8 5/8" to 2359' cemented.

5 1/2" to 5567' cemented Top perforations 5406'

Plug bottom w/ 25 sacks cement Top of cement 5100'

Mud 5100' to 500' Spotted 50 sacks cement 500' to 400'

Mud 400' to 40' Plug, Hulls & 20 sacks cement 40' to 0'

Company, Pump Pulled 3138' of 5 1/2" casing

Pulled 975' of 8 5/8" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edgar J. Lee*
Well Plugging Supervisor

DATE 6/12/68
INV. NO. 1733-W