

15-025-10139-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma, City, Oklahoma

Lease Name J.C. Harper Well No. 8

Location NE NE Sec. 3 Twp. 34 Rge. 21 (N) (W)

County Clark Total Depth 5590'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Gayle E. Toland
Box

Address: 94336, Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 3:00PM Day 17 Month 6 Year 1968

The Above well was plugged as follows:

13 3/8" to 400' circulated w/ cement. 8 5/8" to 2312' cemented

5 1/2" to 5590' cemented. Top perforations 5426'

Plug bottom w/ 30 sacks cement Top of cement 5000'

Mud 5000' to 400' Spotted 50 sacks cement 400' to 300'

Mud 300' to 45' Plug, Hulls & 15 sacks cement 45' to 0'

Company Pump Pulled 983' of 8 5/8" casing.

Pulled 3613' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar E. Eves
Well Plugging Supervisor

INVOICED

DATE 6/20/68
INV. NO. 7976-11