

15-025-10140-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 7 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma City, Oklahoma 73118

Lease Name J.C. Harper Well No. 9

Location NW NW Sec. 3 Twp. 34 Rge. 21 (E) (W)

County Clark Total Depth 5497'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Gayle E. Toland

Address: Box 94336, Oklahoma City, Okla. License No. 539

Operation Completed: Hour 1:00 Pm Day 3 Month 6 Year 1968

The Above well was plugged as follows:

13 3/8" to 501' circulated w/ cement, 8 5/8" to 2341' cemented.

5 1/2" to 5495' cemented Top perforations 5396'

Plug bottom w/ 30 sacks cement Top of cement 5000'

Mud 5000' to 500' Spotted 50 sacks cement 500' to 425'

Mud 425' to 40' Plug, Hulls & 20 sacks cement 40' to 0'

Company Pump Pulled 3835' of 5 1/2" casing

Pulled 823' of 8 5/8" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Lewis  
Well Plugging Supervisor

DATE 6/7/68  
INV. NO: 4901-W