

15-025-10141-00-00

Form CP-3  
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 19 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Ashland Oil & Refining Co.  
Complete Address: Box 18695, Oklahoma City, Oklahoma 73118  
Lease Name J.C. Harper Well No. 15  
Location SW NW Sec. 3 Twp. 34 Rge. 21 ~~20~~ (W)  
County Clark Total Depth 5510'  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated: None  
Plugging Contractor: Gayle E. Toland  
Address: Box 94336, Oklahoma City, Oklahoma License No. 539  
Operation Completed: Hour 3:00PM Day 11 Month 7 Year 1968

The Above well was plugged as follows:

13 3/8" to 500' circulated w/ cement. 8 5/8" to 2385' cemented.  
5 1/2" to 5510' cemented. Top perforations 5402'  
Plug bottom w/ 30 sacks cement Top of cement 4800'  
Mud 4800' to 500' Spotted 50 sacks cement 500' to 400'  
Mud 400' to 40' Plug, Halls & 20 sacks cement 40' to 0'.  
Getco Pump Co. Pulled 892' of 8 5/8" casing  
Pulled 3304' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Love  
Well Plugging Supervisor

INVOICED  
DATE 7/19/68  
INV. NO. 8141-W