


15-191-00152-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Sumner County, Sec. 22 Twp. 34S Rge. (E) 2 (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines NE SE NW
Lease Owner Herndon Drilling Company
Lease Name Allen Estate Well No. 1
Office Address P. O. Box 489, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-5-61 19
Application for plugging filed 3-5-61 19
Application for plugging approved 3-5-61 19
Plugging commenced 3-5-61 19
Plugging completed 3-5-61 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham, Winfield, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4530 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 240 feet to 30 feet for each plug set.

Hole was filled to 240' w/Rotary Mud; 20 sx. spotted on plug.
Hole was filled to 30' -- bottom of cellar plug set and 10 sx. mixed.
Well was plugged w/H. O. W. C.

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Oil Well Cementing Co., Winfield, Kansas
Address _____

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
Tom Elliott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Tom Elliott
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of March, 1961

Johnnie Alene Frese
Johnnie Alene Frese Notary Public.

My commission expires June 19, 1961

15-191-00152-00-00

R

WELL LOG

Well: ALLEN ESTATE NO. 1
 Location: NE SE NW, Sec. 22-34S-2W,
 Sumner County, Kansas
 Owner: Herndon Drilling Company, et al

Spudding date: 2-12-61
 Date casing set: 2-13-61
 Date rotary completed: 3-5-61
 Date cable completed:

FROM	TO	FORMATION	REMARKS
0	487	Surface Hole	Ran 16 joints 9-5/8" H-40 32#
487	565	Lime & Sand	Lone Star Casing. Set @ 487',
565	3350	Lime & Shale	cemented w/400 sx. Common Cement,
3350	3435	Sand & Shale	2% CC added.
3435	3502	Lime	
3502	3578	Lime & Shale	
3578	3654	Lime	
3654	3732	Lime & Shale	
3732	3798	Lime	
3798	3895	Lime & Shale	
3895	3960	Lime	
3960	4077	Lime & Shale	
4077	4105	Lime	
4105	4154	Lime & Shale	
4154	4447	Lime	
4447	4464	Lime & Shale	
4464	4494	Shale	
4494	4516	Lime & Shale	
4516	4523	Shale & Sand	
4523	4530	Sand	
	4530	Total Depth	1st plug @ 240' w/20 sx. cement. 2nd plug @ 30' w/10 sx. cement. Plugged rat hole & mouse hole w/20 sx. each.

RECEIVED
 STATE CORPORATION COMMISSION

MAR 15 1961

CONSERVATION DIVISION
 Wichita, Kansas

Subscribed and sworn to before me this 13th
 day of March, 1961

I certify the above and foregoing to be a true and exact copy
 of the original driller's log on the Allen Estate No. 1

HERNDON DRILLING COMPANY

Johnnie Alene Reese
 Notary Public
 My commission expires:
 June 19, 1961

By: *Patsy M. Nearing*
 Title: Patsy M. Nearing, Asst. Secty.