

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sumner County, Sec. 23 Twp. 34S Rge. (E) 2 (W)

Location as "NE/CNW/SW" or footage from lines E/2 SE NW

Lease Owner ALPINE OIL & ROYALTY CO., INC.

Lease Name Douglas Well No. 1

Office Address 1100 Bitting Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed August 6th 19 48

Application for plugging filed September 8th 19 52

Application for plugging approved September 8th 19 52


Plugging commenced September 9th 19 52

Plugging completed September 10th 19 52

Reason for abandonment of well or producing formation Well no longer able to produce in commercial quantities

If a producing well is abandoned, date of last production February 7th 19 52

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. G. Buffington

Producing formation Simpson sand Depth to top 4474 Bottom 4480 Total Depth of Well 4480 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10"	397'	cemented
				5 1/2"	4476'	2260'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1952
CONSERVATION DIVISION
Wichita, Kansas

Plugged back with crushed rock from 4480' to 4465'. Dumped 6 sacks of cement at 4465', with dump bailer, top of cement 4423'. Pumped 10 sacks of aquagel and 100 sacks of cement in 10" casing for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor MILLER CASING PULLING COMPANY
Address Box 711 Great Bend, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss. Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul
1100 Bitting Building Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September, 19 52

My commission expires March 7th, 1955 Jo Ann Braun Notary Public.

PLUGGING
FILE SEC 23 T 34 R 2W
BOOK PAGE 43 LINE 9

WELL LOG

Alpine Oil & Royalty Co., Inc.

Contractor: Quaker Drilling Co., Inc.

Elevation: 1102 feet

Douglas No. 1
E/2 SE NW Sec. 23-34S-2W
Sumner County, Kansas

Comm: 6-29-48
Comp: 8-1-48
Prod: 50 barrels

Casing Record:

10" 397' cemented with 225 sacks cement

(Figures Indicate Bottom of Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION</u>	<u>DEPTH</u>
Surface Clay & Sand	71	Cherty Lime & Shale	4064
Blue Shale & Shells	190	Mississippi Lime	4089
Shale & Shells	270	Lime & Chert	4114
Red Rock	280	Shale & Chert	4133
Lime - Hard	290	Lime & Chert	4139
Shale & Shells	390	Chert	4149
Lime	404	Lime & Chert	4242
Red Rock	405	Cherty Lime & Shale	4267
Shale & Shells	860	Chert	4273
Sandy Lime	1075	Shale & Lime	4294
Lime	1355	Brown Lime	4307
Shale & Shells	1860	Brown Lime & Shale	4325
Shale & Lime	2295	Chert, Lime & Shale	4250
Shale	2390	Black Chert	4359
Lime - Hard	2475	Black Cherty Lime	4363
Shale & Lime	2560	Cherty Lime	4369
Shale	2616	Black Chert & Lime	4375
Dark Red Shale	2640	Chert & Cherty Lime	4384
Sand	2690	Cherty Lime	4406
Lime & Shale	2875	Grey Shale	4455
Sand	2885	Lime & Shale	4474
Shale	2900	Sand	4480 TD
Brown Dense Limestone	2915		
Shale	2930	<u>FORMATION TOPS</u>	
Limestone	2940	Stalnaker	2937
Sandstone	2950	Kansas City	3412
Shale	2965	Mississippi	4059
Sand, Lime & Shale	3045	Kinderhook	4404
Shale & Lime	4025	Simpson Sand	4474

I hereby certify that the above is a true and correct copy of Driller's Log of well drilled in the E/2 SE NW of Section 23, Township 34 South, Range 2 West, Sumner County, Kansas.

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 - 1952
CONSERVATION DIVISION
Wichita, Kansas

ALPINE OIL & ROYALTY CO., INC.

BY _____
Secretary-Treasurer

Subscribed and sworn to before me this _____ day of August, 1948.

PLUGGING
FILE SEC 23 T 34 R 26
BOOK PAGE 43 LINE 9

My commission expires June 18, 1952

Notary Public