

15-191-30195-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Sumner County. Sec. 24 Twp. 34S Rge. 2 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C SW NW

Lease Owner Alyward Drlg. Co.

Lease Name Rains Well No. 1

Office Address 909 First Nat'l. Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-18 19 67

Application for plugging filed 1-18 19 67

Application for plugging approved 1-18 19 67

Plugging commenced 1-18 19 67

Plugging completed 1-18 19 67

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Howard Hess

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4174 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	252'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1967

CONSERVATION DIVISION
Wichita, Kansas

Hole filled with heavy rotary mud to 170'. Bridge at 170 ft. with hulls and 20 sack cement. Hole filled with mud to 35'. Bridge at 35 ft. with hulls and 8 sacks cement. Rathole capped with 2 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor WHITE & ELLIS DRILLING, INC. License #209

Address Box 448, El Dorado, Kansas 67042

STATE OF Kansas, COUNTY OF Butler, ss.

Ernest Sifford, employee of contractor (employee of contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
Box 448, El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of January, 19 67

My commission expires September 26, 1968

L.B. Amer
Notary Public.

CASING RECORD

8, 5/8

252' Cemented
w/200 sacks

15-191-30195-00-00

Location: C SW NW
Section: 24-34S- 2W
Sumner County, Kansas
Farm: Rains #1
Well Owner: Alyward Drlg. Co.
Contractor: WHITE & ELLIS
DRILLING, INC.
Commenced: 1-6-67
Completed: 1-18-67

T. D. 4174'
Kelly Bushing Measurement 5' above ground level.

<u>FORMATION</u>	<u>DEPTH</u>
Shale & Shells	0-259
Shale	4600
Anhydrite	569
Anhydrite & Shale	830
Lime	910
Shale	1000
Lime & Shale	1490
Shale	1670
Shale & Lime stks.	1895
Shale & Lime	2088
Shale	2136
Sand	2190
Lime	2520
Lime & Shale	2660
Lime	2690
Shale	2770
Sand	2845
Shale	2915
Sand & Shale	3100
Lime & Shale	3180
Shale	3375
Sand	3385
Sand & Shale	3450
Sand	3460
Shale	3480
Lime	3667
Shale & Lime	3743
Lime	3830
Lime & Shale	3930
Shale	4034
Lime & Shale	4064
Shale & Lime	4118
Lime	4174

<u>TOPS</u>	
Anhydrite	460
Severy Sand	2136
Topeka	2190
Kansas City	3480
Mississippi	4118

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1967

CONSERVATION DIVISION
Wichita, Kansas

Dry Hole, Plugged
& Abandoned