

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-20,705-000

LEASE NAME Worthington A

WELL NUMBER 4

SPOT LOCATION 1320' FWL  
1830' FSL

SEC. 2 TWP. 33 RGE. 43 NW 1/4 (W)

COUNTY Morton

Date Well Completed 8-18-84

Plugging Commenced 8-15-84

Plugging Completed 8-18-84

LEASE OPERATOR Cities Service Oil & Gas Corp.

ADDRESS 3545 N.W. 58th St., Okla. City, Okla. 73112

PHONE # (405) 949-4400 OPERATORS LICENSE NO. 5447

Character of Well D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #1

Is ACO-1 filed? Yes If not, is well log attached?

Producing formation None Depth to top bottom T.D. 5050

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	1360'	None
				5 1/2"	5044'	2887'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Set Baker 5 1/2" CIBP @ 4540' K.B., Dumped 25 sx. cmt. on top of CIBP. Got 29" stretch on 1000.00 lbs., load hole with mud, shot pipe at 2690', pull 1 jt. mix & pump 16 bbls. 9.5# mud and 50 sks. common cement to 2590' with 64 bbls. 9.5# mud, pull to 1410' circulate with 16 bbls. 9.5# mud, mix & pump 50 sks. common cement to 1310' with 32 bbls. 9.5# mud, pull to 700', mix & pump 30 sks. common cement to 600' with 15 bbls. 9.5# mud, pull rest of pipe, cement top of surface with 10 sks common cement from 40' to 4'. Cut off 8 5/8" csq. @ 4' and welded (If additional description is necessary, use BACK of this form.) plate on top of CQS Well P & A to state specs. 8-18-84.

Name of Plugging Contractor Daco, Inc.

License No. 38

Address P.O. Drawer 3010, Borger, TX 79008-3010

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

SEP 26 1984

Delbert G. Oliver (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Delbert G. Oliver  
(Address) 3545 NW. 58th Street  
Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 24 day of Sept., 1984

My Commission expires: 6-12-88

Notary Public