

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-20674-00-00

LEASE NAME Soupiset C

WELL NUMBER 1

SPOT LOCATION 660' FSL

SEC. 2 TWP. 33 RGE. 43 W43N33E

COUNTY Morton

Date Well Completed 10-12-83

Plugging Commenced 8-13-84

Plugging Completed 8-16-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cities Service Oil & Gas Corp.

ADDRESS 3545 N.W. 58th St., Okla. City, Okla 73112

PHONE # (405) 949-4400 OPERATORS LICENSE NO. 5447

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #1

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation None Depth to top _____ bottom _____ T.D. 5080'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	1358'	None
				5 1/2"	3868'	2253'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Got hold of 5 1/2", got 25" stretch on 100,000 lbs., load hole with 9.5# mud, shot pipe at 2427', pipe pulled at approx. 14', hung up so shot again at 2201', pulled 1 ft., circulate hole with 16 bbls. 9.5# mud, mix & pump 50 sks, common cement to 2100' with 50 bbls. 9.5# mud, pull pipe to 1408', mix & pump 50 sks, common cement to 1308' with 32 bbls. 9.5# mud, pull to 700', mix & pump 30 sks, common cement to 600' with 11 bbls. 9.5# mud, pull rest of pipe, then cement top of surface with 10 sks, common cement from 40' to (if additional description is necessary, use BACK of this form.) 4'. Cut off 8 5/8" CSG. @ 4'. Welded on plate P & A 8-16-84

Name of Plugging Contractor Daco, Inc. License No. 38
Address P.O. Drawer 3010, Borger, Texas 79008-3010

STATE OF Oklahoma COUNTY OF Oklahoma, ss. RECEIVED
STATE CORPORATION COMMISSION

D. G. Oliver (employee of operator) or SFP 26 1984
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) D. G. Oliver
3545 N.W. 58th St.
(Address) Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 24 day of Sept., 1984

My Commission expires: 6-12-88

Joyce L. Porter
Notary Public