

API NUMBER 15-129-20763-00-00

LEASE NAME Worthington

WELL NUMBER 1-B

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 3 TWP. 33 RGE. 43 (W) or (E)

COUNTY Morton

Date Well Completed 8-28-85

Plugging Commenced 1-31-2000

Plugging Completed 2-2-2000

FEB 14 2000

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

CONSERVATION DIVISION
 Wichita, Kansas

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N Kansas PO Box 2528 Liberal, KS. 67905

PHONE# (316) 629-4206 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-31-2000 (date)

by Gary Winters & Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation Morrow Depth to Top 4617 Bottom 4640 T.D. 5066'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1372	-
				5 1/2	5066	2802

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pressure tested CIBP @ 4600 to 500 PSI. Recov. 2802 5 1/2. Circ. hole w/mud & mixed 25 sx plug from 2800 to 2700. 50 sx 1400 to 1300. 40 sx 450 to 350 10 sx 40 to 0 Cut off & capped 8 5/8 3 ft. below G.L.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address: Box 506 Liberal, KS 67905

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.


STATE OF Kansas COUNTY OF Seward, ss.

Kenny L. Andrews (Employee of Operator) or (Operator) or above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED AND SWORN TO before me this 11th day of February, 2000



My Commission Expires: Oct. 1, 2001

Anita Peterson
 Notary Public

