

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2125
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-21339-00-00

LEASE NAME Cosgrove

WELL NUMBER 1-4

4950 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 4 TWP. 33 RGE. 33 or (W)

COUNTY Seward

Date Well Completed 01-03-94

Plugging Commenced 12-12-95

Plugging Completed 12-14-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Wheeler Energy Co.

ADDRESS P. O. Box 1439, Tulsa, OK 74101-1439

PHONE#(918) 587-7474 OPERATORS LICENSE NO. 7203

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-13-95 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation Morrow-Chester Depth to Top 5930 Bottom 5504 T.D. 6200

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

JAN 11 8 1996

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Oil	1684	0	8 7/8	1,684	
Chester	Oil	6198	0	4 1/2	6,198	1700

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each s

Set CIBP @ 5530. Recovered 1700 ft 4 1/2.

Circ hole w/mud & mixed 50 sx cement plug from 1700 to 1550. Pull 4 1/2 to 700.

Mixed 40 sx plug from 700 to 600. Pull to 40. Mixed 10 sx plug from 40 to 0.

Cut off & cap 8 7/8 3 ft. below ground level. Used mud between plugs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Wheeler Energy

STATE OF Kansas COUNTY OF Seward, ss.

Keith Hill

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed. The same are true and correct, so help me God.

(Signature) Keith Hill

(Address) Crown Consulting, Inc.
P. O. Box 1816, Liberal, KS 67905-1816

SUBSCRIBED AND SWORN TO before me this 5th day of January, 19 96

Helen M. Smith
Notary Public

My Commission Expires:

NOTARY PUBLIC, State of Kansas
Seward County
HELEN M. SMITH
My Appt. Exp. 3-5-97

Form C
Revised 05