

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR D.C. Dudley & Associates

ADDRESS 1776 Lincoln St., #904

PHONE# (303) 861-0800 OPERATORS LICENSE NO. 30197

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-15-92 (date)

by Wichita, #2 (KCC District Agent's Name).

Is ACO-1 filed? to be per CP1 not, is well log attached? to be per CP1

Producing Formation simpson Depth to Top 4842 Bottom 4873 T.D. 4895

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	water	0	455	8 5/8	455	none
	water	0	4895	4 1/2	4895	3100 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s sand back to 4790 ft, spot 4 sx cement, shoot pipe at 4100, shoot at 3900, shoot at 3800 ft, shoot at 3100, pull to 575 ft and pump 40 sx plug, pull to 60 ft and pump cement to surface, gel spacer used, United Cementing #3801 60/40 poz 4% Gel

Name of Plugging Contractor VAL Energy, Inc. License No. 5822

Address Box 322 Haysville, Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: D.C. Dudley & Associates

STATE OF Kansas COUNTY OF Sedgwick, ss.

K. Todd Allam (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fac- statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.


(Signature) K Todd Allam

(Address) Wichita, Ks.

SUBSCRIBED AND SWORN TO before me this 24th day of JULY 1992

Gary D. Stearns  
Notary Public JUL 20 1992

USE ONLY ONE SIDE OF EACH FORM



RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
Revised 05-