

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

RECEIVED  
STATE CORPORATION COMMISSION

NOV 13 1995

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API# 15-175-21339-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Wheeler Energy Co. KCC LICENSE # 7203  
(owner/company name) (operator's)  
ADDRESS P. O. Box 1439 CITY Tulsa  
STATE OK ZIP CODE 74101-1439 CONTACT PHONE # (918) 587-7474  
LEASE Cosgrove WELL# 1-4 SEC. 4 T. 33S R. 33 (East/West)  
-N/2 -NE/4 -NW/4 SPOT LOCATION/QQQQ COUNTY Seward

330 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)  
1980 FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

check One: OIL WELL X GAS WELL     D&A     SWD/ENHR WELL     DOCKET#    

CONDUCTOR CASING SIZE     SET AT     CEMENTED WITH     SACKS  
SURFACE CASING SIZE 8-5/8" SET AT 1684' CEMENTED WITH 665 SACKS  
PRODUCTION CASING SIZE 4-1/2" SET AT 6198' CEMENTED WITH 1st stage 605 SACKS  
2nd stage 260

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 6034-6041' 2 SPF 5580-5584' 4 SPF  
DV tool at 3096'

ELEVATION 2823.5 T.D. 6200' PSTD 6133' ANHYDRITE DEPTH 1600'  
(G.L. (K.E.)) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR     CASING LEAK     JUNK IN HOLE    

PROPOSED METHOD OF PLUGGING Set CIBP at 5530', 2 sacks cement on top of CIBP,  
50 sack plug at 1684', 30 sack plug  
at 720', 10 sack plug 40-4', cut off 8-5/8" casing at ground level and weld on

ID plate, orders from Steve Durant  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why?    

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Crown Consulting, Inc. PHONE# ( ) (316) 624-0156

ADDRESS P. O. Box 1816 city/State Liberal, KS 67905-1816

PLUGGING CONTRACTOR Sargent's Casing Pullers KCC LICENSE # 6547  
(company name) (contractor's)

ADDRESS 620 S. Lincoln, Liberal, KS 67901 PHONE # ( ) (316) 624-7455

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 11-15-95

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11-03-95 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)

6/96

6/96



## Kansas Corporation Commission

Bill Graves, Governor Susan M. Selsam, Chair F.S. Jack Alexander, Commissioner Timothy E. McKee, Commissioner  
Judith McConnell, Executive Director

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

November 14, 1995

Wheeler Energy Co  
P O Box 1439  
Tulsa OK 74101-1439

Cosgrove #1-4  
API 15-175-21,339  
330 FNL 1980 FWL  
Sec. 04-33S-33W  
Seward County

Dear Crown Consulting, Inc.,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City KS 67801  
(316) 225-6760