

LEASE NAME Worthington A

WELL NUMBER 1

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 2 TWP. 33 RGE. 43 (S) or (W)

COUNTY Morton

Date Well Completed 12-13-82

Plugging Commenced 10-21-98

Plugging Completed 10-23-98

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Oxy USA

ADDRESS Box 2528, Liberal KS 67905

PHONE# (316) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-21-98 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 4569 Bottom 4974 T.D. 5100

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 20 | 43 | - |
| | | | | 8 5/8 | 1359 | - |
| | | | | 5 1/2 | 5099 | 2419 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s.
Mixed 3 SX hulls & 25 SX cmt. to plug perfs. from 4569 to 4369. Recovered 2419 5 1/2. Mixed 30 SX cmt. plug 2400 to 2300 50 SX 1380 to 1230 30 SX 450 to 350 10 SX 40 tool cut off & capped 8 5/8 ft. below G.L.

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address Box 506 Liberal KS 67905

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy U.S.A. Inc


STATE OF Kansas COUNTY OF Seward, ss.

Carrol M. Wylie (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) C.M. Wylie

(Address) Box 2528 Liberal KS 67905

SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 98



Aleta J. Arnold
 Notary Public

My Commission Expires: 2-14-99

USE ONLY ONE SIDE OF EACH FORM