


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD 15-077-00969-0000



Locate well correctly on above
Section Plat

Harper County, Sec. 25 Twp. 31 Rge. 9 (E) (W) X
Location as "NE/CNW/SE/SW" or footage from lines C-E / 2-SE / 4-SW / 4
Lease Owner Mull Drlg. Co., Inc.
Lease Name Antrim-Campbell Well No. 1
Office Address Box 328 Attica, Kansas 67009
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced August 15, 1972
Plugging completed August 21, 1972
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4363' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	158	None
				5 1/2	4363	2566.49'


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured T. D. Dumped sand to 4325' and 5 sacks cement. Shot casing at 3300', 2300', 3100', 3000', 2900', 2800', 2700', 2600', and 2550'. Pulled a total of 82 jts. of 5 1/2" casing. Built a rock bridge at 175'. Plugged with 4 yards readymix concrete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.
Address Box 698 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) James W. Rockhold
Box 698 Great Bend, Ks. 67530 James W. Rockhold

(Address) August 1972

SUBSCRIBED AND SWORN TO before me this 28th day of

Cathy Miller
Cathy Miller, Notary Public.

My commission expires September 30, 1975

15-077-60969-0000

ROTARY DRILLERS LOG

COMPANY : PURCELL-MULL DRILLING CO., INC. ROTARY DRILLING COMMENCED: 8-28-55
 WICHITA, KANSAS

CONTRACTOR : Purcell-Mull Drilling Co., Inc. ROTARY DRILLING COMPLETED: 9-10-55
 Wichita, Kansas

CASING RECORD : Set 8 5/8" @ 158' cemented with 150 sacks cement
 LOCATION: ANTRIM-CAMPBELL #1
 C (E/2) SE/4 SW/4
 Sec. 25-31S-9W
 Harper County, Kansas

Set 5 1/2" @ 4363' cemented with 150 sacks cement

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

Sand	20	Lime	3187
Red Bed	158	Lime & Shale	3734
Red Bed & Shells	500	Shale & Lime	3946
Shale & Shells	1250	Lime	4157
Shale & Lime	1495	Lime & Shale	4330
Lime & Shale	1645	Shale & Lime	4337
Lime	1825	Lime (Miss)	4363 R.T.D.
Lime & Shale	2235		
Shale & Lime	2610		
Lime & Shale	2735		
Shale & Lime	3096		

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 16 1952
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Purcell-Mull Drilling Co., Inc.

Frank H. Purcell
 FRANK H. PURCELL, SECRETARY

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 19th day of September, 1955

Ethel Zimmerman
 NOTARY PUBLIC

MY COMMISSION EXPIRES: JANUARY 28, 1957.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 16 1952
 CONSERVATION DIVISION
 Wichita, Kansas

