


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 26 Twp. 31 NE Rge. 9W (E) (W)

Location as "NE/CNWSW" or footage from lines NE SE SE
Lease Owner Mull Drilling Company
Lease Name Broce Well No. 1
Office Address 670 Fourth Nat'l Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed May 1 1962
Application for plugging approved May 1 1962
Plugging commenced May 1 1962
Plugging completed May 1 1962
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel Pretty Prairie, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4133 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	220	
				5 1/2		3234

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cleaned out cellar. Measured T.D. Sanded to 3920. Dumped 5 sacks cement. Worked pipe and shot well @ 3800-3700. Worked pipe and shot well @ 3600-3500-3400-3300-3210. Pulled pipe and plugged well with mud. Built rock bridge @ 200'. Dumped 20 sacks cement and filled hole and rock bridge. Capped well with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. (So help me God.)

(Signature) J. O. Forbes
(Address) _____

SUBSCRIBED AND SWORN TO before me this 11 day of May, 1962

My commission expires April 8, 1965
Arthur J. Hubil Notary Public.



15-077-00019-0000

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
608 East Murdock, Wichita, Kansas


COPY

Company - FURCELL-MULL DRILLING CO., INC.
Farm - Broce No. 1

SEC. 26 T. 31 R. 9W
NE 5& SE

Total Depth. 4433
Comm. 2-27-55 Comp. 3-13-55
Shot or Treated.
Contractor - Furcell-Mull Drig Co., Inc.
Issued. 5-28-55

County Harper KANSAS



CASING:
8 5/8" 214' cem w/150 sx
5 1/2" 4433' cem w/250 sx

Elevation: 1599 RB

Production: 335 bbls

Meas. from top of Rotary bushing.

Figures indicate Bottom of Formations.

sand, clay	40
sand	100
red rock	375
red rock, shale	495
redbed	765
shale, shells	1190
anhydrite	1200
shale, salt, lime	1365
lime, shale	1795
lime	1935
lime & shale	2885
lime	2975
lime, shale	3562
sand	3681
lime	4174
shale, lime	4422
chat	4433
Total Depth	RTD

Tops:	
Heebner	3435
Lansing	3649
Mississipi	4421

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1962
CONSERVATION DIVISION
Wichita, Kansas