


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-077-10109-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Harper County, Sec. 26 Twp. 31S Rge. (E) 9 (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner: Champlin Oil & Refining Co.
Lease Name: Rall Well No. 1
Office Address: Room 306, Koch Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed June 1, 19 55
Application for plugging filed March 19, 19 57
Application for plugging approved March 20, 19 57
Plugging commenced March 20, 19 57
Plugging completed March 28, 19 57
Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production July 22, 19 56
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4426 Feet
Show depth and thickness of all water, oil and gas formations. P.B.T.D.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9 5/8" OD	261'	None
				5 1/2" OD	4422'	3409'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crushed rock to 4380', dumped 5 sax cement @ 4380' with dump bailer. Top of cement, 4345'. Pumped in 44 sax Gel-mud @ 1800' by Halliburton. Filled hole with mud to 250', set rock bridge, dumped 25 sax cement. Top of cement 200'. Filled hole with mud to 20', set rock bridge, dumped 10 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Miller Casing Pulling Co.
Address: Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J.W. Meyers (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J.W. Meyers*
Room 306, Koch Bldg, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 3rd day of April, 19 57

My commission expires 2-23-59

Cecil J. Yeisley Jr.
Notary Public.

PLUGGING
FILE SEC. 26 T. 31 R. 9W
BOOK PAGE 149 LINE 18

RECEIVED
STATE CORPORATION COMMISSION

APR 4 - 1957

CONSERVATION DIVISION
Wichita, Kansas

TO KANSAS CORPORATION COMMISSION
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

15-077-10109-0000

County Harper SEC. 26 TWP. 31 RGE.

COMPANY OPERATING Champlin Oil & Refining Co.

OFFICE ADDRESS Room 306, Koch Bldg., Wichita, Kansas

FARM NAME Frank D. Rall WELL NO. 1

WELL LOCATED SW-SW-SW

CHARACTER OF WELL Oil/Gas

DRILLING COMMENCED 5-17-55 DRILLING COMPLETED 6-1-55

SIZE	WEIGHT	THDS	MAKE	FT.	AMOUNT PULLED	CEMENT
9 5/8"OD	28#	8V	Smls.	261	none	165 sks
5 1/2"OD	14#	8rd	Smls.	4422	none	150 sks

FORMATION RECORD

TOPS	BOTTOM		TOPS	BOTTOM
0	261	Red Bed Anhydrite		
261	1620	Shale		
1620	1934	Shale & Lime		
1934	2030	Shale & Anhydrite		
2030	2338	Shale & Shells		
2338	2910	Shale		
2910	3000	Shale & Shells		
3000	3149	Shale-Lime-Shells		
3149	3597	Shale-Lime		
3597	4426	Lime		
4426		TOTAL DEPTH		

RECEIVED
 STATE CORPORATION COMMISSION

MAR 20 1957

CONSERVATION DIVISION

Subscribed and sworn to before me
 this 19th day of March, 1957
 Wichita, Kansas

My commission expires 2-22-61

J. W. Meyers
 Superintendent
 J. W. Meyers
N. Kenneth Stivers
 Notary Public
 N. Kenneth Stivers

PLUGGING
 FILE SEC 26 T 31 R 9W
 BOOK PAGE 149 LI E 18