


15-077-10177-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

HARPER County. Sec. 26 Twp. 31S Rge. 9W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner SANTA-FE PIPE & SUPPLY, INC.
Lease Name RALL "C" Well No. 1
Office Address BOX 562, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) GAS
Date well completed NOVEMBER 15 1960
Application for plugging filed DECEMBER 9 1966
Application for plugging approved DECEMBER 12, 1966
Plugging commenced JANUARY 13 1967
Plugging completed JANUARY 20 1967
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production NOT AVAILABLE
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. ARCHIE ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4504 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	221	NONE
				5 1/2	4502	3645

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4504 - 4467 - PLUG
4467 - 4400 - SAND
4400 - 4360 - 5 SACKS CEMENT
4360 - 220 - MUD
220 - 210 - ROCK BRIDGE
210 - 135 - 25 SACKS CEMENT
135 - 40 - MUD
40 - 30 - ROCK BRIDGE
30 - BASE - 10 SACKS CEMENT

RECEIVED
JAN 30 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T.L. NUTT (Employer/owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T.L. Nutt
BOX 562, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 28TH day of JANUARY, 1967
Mary M. Guenier
Notary Public.
My commission expires JULY 31, 1970

File Copy
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas

LOCATION: RALL "C" #1 - NW NW SW
Sec. 26-31S-9W, Harper County, Kansas

Rotary Drilling Commenced 11-2-60
Rotary Drilling Completed 11-15-60

15-077-10177-0000

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Ran 8 jts. 20# 8 5/8" T&C csg. Set @ 221' w/150 sks cement. Circ.
Ran 140 jts. 14# 5 1/2" J-55 Smls csg. Set @ 4502.85' w/100 sks.
cement.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

75'	Sand	<u>Circulate for Samples</u>
255	Red rock	
1000	Shale, shell, red rock	4410'
1375	Shale, shells, clays, Gypsum	4420
1600	Lime, shale, salt	4423
1735	Lime, shale	4433
1900	Lime	4443
2280	Lime, shale	4453
2770	Shale, lime	4463
3710	Lime, shale	4504
3829	Lime	
3900	Lime, shale	
3965	Lime, shly	<u>Slope Test</u>
4080	Lime	
4121	Limestone	1500' 0°
4208	Lime	2000 0°
4403	Lime, shale	3000 0°
4504	Miss. T.D.	4000 0°

S.L.M.

150' OK
2000 OK
3500 OK
4000 OK
4500 OK

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By *C. W. Sebitts*
Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 21st day of November, 1960, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: March 7, 1964

Marilyn A. Davis
Notary Public
Marilyn A. Davis