

15-077-20494-2000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Harper County, Sec. 26 Twp. 31S Rge. 9 ~~xx~~W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SW SE

Lease Owner Bill J. Dutton Oil Co.
Lease Name Jacobs 'A' Well No. 1
Office Address 620 1st Natl. Center, Hutchinson, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Locate well correctly on above
Section Plot

Date Well completed 10-9 1978
Application for plugging filed 10-9 1978
Application for plugging approved 10-9 1978
Plugging commenced 10-9 1978
Plugging completed 10-9 1978

Reason for abandonment of well or producing formation
no commercial quantities of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Wm. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4460
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface hole	shale	surf	207	8-5/8"	205'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug-set.

RECEIVED
STATE CORPORATION COMMISSION

OCT 18 1978

CONSERVATION DIVISION
Wichita, Kansas

Fluid to 210', plug, 40 sx
Fluid to 40', plug, 12 sx
3 sx in rat hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
515 R. H. Garvey Building
Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ella Priess (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ella Priess
Suite 515, R.H. Garvey Bldg., Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of October, 19 78

My commission expires April 30, 1979

Dorothy L. Schmidt
Dorothy L. Schmidt Notary Public.

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1979

DRILLER'S LOG

BILL J. DUTTON OIL CO.
No. 1 Jacobs 'A'
SE SW SE Sec. 26-31S-9W
Harper Co., Ks.

15-077-20494-0000

Surface Casing: 205' of 8-5/8"
cmtd w/150 sx common, 2% gel, 3% cc
10-3-78

Commenced: 10-3-78
Completed: 10-9-78

FORMATION

DEPTH

Surface Hole	0 - 207
Sand	207 - 668
Sand & Shale	668 - 1220
Shale, Sand & Lime	1220 - 1730
Sand, Shale & Lime	1730 - 2005
Shale & Lime	2005 - 2330
Shale, Lime & Sand	2330 - 2628
Shale & Lime	2628 - 2843
Lime & Shale	2843 - 3130
Sand, Shale & Lime	3130 - 3595
Sand & Shale	3595 - 3860
Lime & Shale	3860 - 4452
Lime	4452 - 4460 RTD

RECEIVED
STATE CORPORATION

OCT 18 1978

CONSERVATION
Topeka, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 11th day of October, 1978.

Dorothy L. Schmidt

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Scottsbluff County, Kansas
My Appl. Exp. April 30, 1979